

## OPTO-ANALOG DEVICES DIVISION ELECTRONIC COMPONENTS GROUP SHARP CORPORATION

# **SPECIFICATION**

DEVICE OPECIFICA	ETON LEOD	
DEVICE SPECIFICA		
	PHOTOTRANSISTOR	
MODEL No.	PT4800E0000F	
	1 146001200001	
Specified for		
Enclosed please find copies of the	e Specifications which consist	s of 10 pages including cover.
After confirmation of the content	ts, please be sure to send back	copy of the Specifications
with approving signature on each	l.	
CUSTOMER'S APPROVAL		PRESENTED
		TIMBELITEE
DATE		DATE
	<del></del>	
		41 0:
BY .		BY ()
	<del></del>	Y. Oda,
		Department General Manager of
		Engineering Dept.,III
		Opto-Analog Devices Div.
		ELECOM Group SHARP CORPORATION

Product name: PHOTOTRANSISTOR

Model No.: PT4800E0000F

1.	These specification sheets include materials protected under copyright of Sharp Corporation ("Sharp")
	Please do not reproduce or cause anyone to reproduce them without Sharp's consent.

2. When using this product, please observe the absolute maximum ratings and the instructions for use outlined in these specification sheets, as well as the precautions mentioned below. Sharp assumes no responsibility for any damage resulting from use of the product which does not comply with the absolute maximum ratings and the instructions included in these specification sheets, and the precautions mentioned below.

#### (Precautions)

(1) This product is designed for use in the following application areas;

· OA equipment · Audio visual equipment · Home appliances

· Telecommunication equipment (Terminal) · Measuring equipment

· Tooling machines · Computers

If the use of the product in the above application areas is for equipment listed in paragraphs (2) or (3), please be sure to observe the precautions given in those respective paragraphs.

(2) Appropriate measures, such as fail-safe design and redundant design considering the safety design of the overall system and equipment, should be taken to ensure reliability and safety when this product is used for equipment which demands high reliability and safety in function and precision, such as ;

· Transportation control and safety equipment (aircraft, train, automobile etc.)

· Traffic signals · Gas leakage sensor breakers · Rescue and security equipment

Other safety equipment

(3) Please do not use this product for equipment which require extremely high reliability and safety in function and precision, such as;

· Space equipment · Telecommunication equipment (for trunk lines)

· Nuclear power control equipment · Medical equipment

- (4) Please contact and consult with a Sharp sales representative if there are any questions regarding interpretation of the above three paragraphs.
- 3. Please contact and consult with a Sharp sales representative for any questions about this product.



#### 1. Application

This specification applies to the outline and characteristics of Silicon phototransistor Model No. PT4800E0000F,

#### 2. Outline

Refer to the attached drawing No. CY12873H02.

#### 3. Ratings and characteristics

Refer to the attached sheet, page 5, 6.

#### 4. Reliability

Refer to the attached sheet, page 7.

#### 5. Outgoing inspection

Refer to the attached sheet, page 8.

#### 6. Supplement

(6-1) Packing

Refer to the attached sheet, page 9.

- (6-2) This product is not designed against electromagnetic and ionized-particle irradiation.
- (6-3) This product shall not contain the following materials.

Also, the following materials shall not be used in the production process for this product.

Materials for ODS: CFC<sub>S</sub>, Halon, Carbon tetrachloride

1.1.1-Trichloroethane (Methyl chloroform)

- (6-4) This product does not contain specific brominated flame retardants such as the PBB and PBDE.
- (6-5) Compliance with each regulation
  - 6.5.1 The RoHS directive(2002/95/EC)

This product complies with the RoHS directive(2002/95/EC).

Object substances: mercury, lead, cadmium, hexavalent chromium, polybrominated biphenyls (PBB)

and polybrominated diphenyl ethers (PBDE)

6.5.2 Content of six substances specified in Management Methods for Control of Pollution Caused by Electronic Information Products Regulation (Chinese: 电子信息产品污染控制管理办法).

1100000 140Bararen (eruntea : 0.1 H. G. HH. 20(471) H. 772 ha).								
	Toxic and hazardous substances							
Category	Lead	Lead Mercury		Hexavalent	Polybrominated	Polybrominated		
Category	(Pb) (Hg)	۱ ۲	Cadmium (Cd)	chromium	biphenyls	diphenyl ethers		
		(Ca)	(Cr <sup>6+</sup> )	(PBB)	(PBDE)			
Phototransistor	1	1	/	1	1	1		

<sup>✓:</sup> indicates that the content of the toxic and hazardous substance in all the homogeneous materials of the part is below the concentration limit requirement as described in SJ/T 11363-2006 standard.

### (6-6) Product mass (Piece): Approximately 0.07g



#### 7. Notes

(7-1) Cleaning conditions:

Solvent cleaning: Solvent temperature 45°C or less Immersion for 3 min or less

Ultrasonic cleaning: The effect to device by ultrasonic cleaning differs by cleaning bath size, ultrasonic power

output, cleaning time, PCB size or device mounting condition etc.

Please test it in actual using condition and confirm that doesn't occur any defect before starting

the ultrasonic cleaning.

The cleaning shall be carried out with solvent below.

Solvent: Ethyl alcohol, Methyl alcohol, Isopropyl alcohol

(7-2) Soldering

The lead pins should be soldered according to the absolute maximum ratings.

While or after soldering, the lead pins shall be free from external force.

This device shall not be soldered with preheat or reflow.

The lead pins surface(solder dip) of this device is using lead-free solder.

Regarding lead-free solder, by the kind of solder, there are cases that separation between land pattern and solder occurs. So please use this device after confirmation of the solder issue by actual conditions.

# SHARP 8.0 2-CO.5 MAXO.1 Resin burr MAX0.3 0.7 2 - 0.9Resin burr MAX0.2 2-0.25<u>:</u>2: 2-0, 45 -0.3 (1)(2.54)1) Unspecified tolerance shall be $\pm 0.2$ . 2) Package: Transparent 3) Dimensions in parenthesis are shown for reference. 4) The thin burr thickness (MAX. 0.05mm) and the gate burr (MAX. 0.3mm) shall not be inclusive to the outline dimensions. 5) Protruded resin 0.3mm MAX. However, the thin burr with a lead attached is 1.8mm MAX. from the resin. Pin name Terminal connection 1 Emitter (2) Collector 兄 度 SCALE 材質 MATERIAL 上 FINISH 名 称 PT4800E0000F Lead pin: Solder dip NAME **Outline Dimensions** Lead: Cu Lead-free solder use Composition (Standard value) 単 位 UNIT Package: Epoxy resin Y 1 2 8 7 3 H 0 2 m m Sn96.5%,Ag3.0%,Cu0.5% DRAWING No.



## 3. Ratings and characteristics

#### 3.1 Absolute maximum ratings

Ta=25°C

Parameter	Symbol	Rating	Unit
Collector-emitter voltage	$V_{CEO}$	35	V
Emitter-collector voltage	V <sub>ECO</sub>	6	V
Collector current	Ic	20	mA
Collector power dissipation	Pc	75	mW
Operating temperature	Topr	-25 to +85	$^{\circ}\!\mathbb{C}$
Storage temperature	Tstg	-40 to +85	$^{\circ}$
* Soldering temperature	Tsol	260	$^{\circ}$

<sup>\*</sup> For 3 seconds MAX. at the position of 1.8mm from the resin edge.

## 3.2 Electro-optical characteristics

Ta=25°C

Parameter	Symbol	MIN.	TYP.	MAX.	Unit	Conditions
Collector current	Ic	0.12	0.4	1.0	mA	*Ee=1mW/cm <sup>2</sup> V <sub>CE</sub> =5V
Dark current	I <sub>CEO</sub>	-	- -	100	nA	Ee=0, V <sub>CE</sub> =20V
Collector-emitter saturation voltage	V <sub>CE(sat)</sub>	-	-	0.4	V	%Ee=10mW/cm <sup>2</sup> Ic=0.5mA
Collector-emitter breakdown voltage	BV <sub>CEO</sub>	35		-	V	Ic=0.1mA Ee=0
Emitter-collector breakdown voltage	BV <sub>ECO</sub>	6	_	-	. <b>V</b>	I <sub>E</sub> =0.01mA Ee=0
Peak sensitivity wavelength	λp	1	800	-	nm	_
Response time (Rise)	tr	-	3.0	-	μs	V <sub>CE</sub> =2V, Ic=2mA
Response time (Fall)	tf	-	3.5	-	μs	$R_L=100\Omega$
Angle of half intensity	θ	-	±35		deg	_


<sup>※</sup> Ee: Irradiance by CIE standard light source A (tungsten lamp)

M In regard to Collector current (Ic), the following ranking shall be carried out. However, the quantity of each rank shall not be prescribed.


Rank	Collector current Ic (mA)					
. A	0.12 to 0.28					
В	0.22 to 0.53					
С	0.42 to 1.0					



## (3.3) Collector power dissipation vs. ambient temperature



## (3.4) Spectral sensitivity (reference)





## 4. Reliability

 $\cdot$  The reliability of products shall satisfy items listed below.

Confidence level: 90%

LTPD: 10 or 20

		F-:1	G1 (-)	
Test Items	Test Conditions	Failure Judgement	Samples (n)	
		Criteria	Defective(C)	
	1 cycle $-40^{\circ}C \longleftrightarrow +85^{\circ}C$	·		
Temperature cycling	(30min) (30min)		n=22, C=0	
	20 cycles test			
High temp. and high humidity storage	+60°C,90%RH, 500h		n=22, C=0	
High temp. storage	+85°C, 500h		n=22, C=0	
Low temp. storage	-40°C, 500h		n=22, C=0	
Operation life	Pc=50mW, Ta=25°C, 500h	Ic $<$ L $\times$ 0.8	n=22, C=0	
Mechanical shock	1000m/s <sup>2</sup> , 6ms, Half sine wave	Ic>U×1.2	11 (7-0	
Mechanical Shock	3 times/ $\pm$ X, $\pm$ Y, $\pm$ Z direction	$I_{CEO}>U\times2.0$	n=11, C=0	
Variable frequency vibration	100 to 2000 to 100Hz/Sweep for 4min 200m/s <sup>2</sup> , 48min/X, Y, Z direction	$V_{CE(sat)} > U \times 1.2$ U: Upper specification limit	n=11, C <b>=</b> 0	
Terminal strength	Weight: 5N	L: Lower specification limit	n=11, C=0	
(Tension)	10 s/each terminal		111,00	
Terminal strength (Bending)	Weight: 2.5N $0^{\circ} \rightarrow 90^{\circ} \rightarrow 0^{\circ} \rightarrow -90^{\circ} \rightarrow 0^{\circ}$ The one test should be performed.		n=11, C=0	
Soldering heat	260±5℃, 5±0.5s Position of 1.8mm from the resin edge.		n=11, C=0	
Solderability	245±5℃, 5±1 s  Position of 1.8mm from the resin edge.  Flux:EC-19S (Tamura kaken corporation)  No pretreatment	Solder shall adhere at less than 95% area of dipped portion.	n=11, C=0	



## 5. Outgoing inspection


(1) Inspection lot

Inspection shall be carried out per each delivery lot.

(2) Inspection method

A single sampling plan, normal inspection level II based on ISO2859 shall be adopted.


Defec	t	Inspection items and test method			AQL(%)			
	1	Disconnection, short						
	2	Inverse polarity on terminal						
	3	Characteristics defect						
		Parameter	Symbol	Judgement criteria		Unit		
		1 arameter	Symbol	MIN.	MAX.	Oint		
Major		Collector current	Ic	0.12	1.0	mA	0.065	
defect		Dark current	$I_{CEO}$	-	100	nA	0.005	
		Collector-emitter	BV <sub>CEO</sub>	35	- ;	v		
		breakdown voltage						
		Emitter-collector BV <sub>ECO</sub>	$BV_{ECO}$	6.0	-	v		
		breakdown voltage	122					
	1	Test conditions refer to	paragraph 3.2.	<del></del> .		,		
	1	Appearance defect		Judgement criteria				
		Parameter						
		Crack		Visible crack irrespective of its position shall be defect.				
		Split, Chip,	One which	One which affects the characteristics				
Minor		Scratch,	of paragrapl	of paragraph 3.2 shall be defect.				
defect		Stain, Blur						
			Foreign ma	Foreign matter except resin shall be defect.				
		Foreign matter	Foreign mat	Foreign matter of 1.0mm or more in resin				
		1 oroigii mattor	or foreign n	natter on the	surface of lig	ht detector		
			shall be defe	ect.				
		Bubble	Visible ones	Visible ones shall be defect.				



② Inner packing material: Vinyl bag (Polyethylene)

③ Quantity: 1000pcs./bag

## 6-1-2 Outer packing



② Outer material: Packing case (Corrugated cardboard),
Cushioning material (Urethane), Cellophane tape

3 Quantity: 5000pcs./box

4 Indication: Model No., quantity and inspection date

(5) Regular packaged mass: Approximately 460g